


္ငံ

MANHOLE STEPS SHALL BE CAST INTO WALLS-TYPICAL

SEE NOTE 9

## PRECAST CONCRETE **VAULT NOTES**

- 1. F'c = 5000 PSI @ 28 DAYS
- 2. f'y = 60,000 PSI.
- 3. VAULTS ARE DESIGNED FOR THE FOLLOWING CONDITION. A. H20 LOADING & 1'-0" COVER + 35% IMPACT B. H20 LL + 0% IMPACT + 5'-0" MAXIMUM EARTH COVER.
- 4. DRILL BYPASS HOLES IN FIELD IF REQ'D.
- 5. PROVIDE K.O. PANELS AT PIPE PASSING THRU WALL. NO REINFORCEMENT SHALL BE PLACED IN K.O. PANEL. MAXIMUM SIZE OF K.O. PANEL TO BE PIPE I.D. + 6" EACH SIDE.
- 6. PROVIDE ADDITIONAL BARS OVER K.O AS SHOWN. SIZE AND NUMBER OF ADDN'L BARS TO BE SAME AS SIZE AND NUMBER OF "M" BARS DISCONTINUED DUE TO KNOCK OUT.
- 7. PROVIDE ADDITIONAL 2-#4 BAR VERTICAL EACH SIDE OF K.O. x 3'0" LONG IN TOP AND BOTTOM BARREL.
- 1" MINIMUM THICK CEMENT MORTAR WEARING COURSE AT SUMP.
- 9. PROVIDE  $2-\#5 \times 5'-0"$  LONG BELOW K.O. 10.SEE W/6.12 FOR VAULT SIZE REQUIRED
- AND METER INSTALLATION DETAILS. 11.ADDITIONAL BARS PROVIDED AROUND K.O. SHALL BE 1" CLEAR OF K.O.



<u>ئ</u>ے|ك

"F	"	"Q"	"R"	"L"	"M"	'N"	"0"
6		6'-0"	6'-0"	#4@18"	#5@12"	#J\\	#4@18"
6		6'-0"	8'-0"	#4@18 <b>"</b>	#5 <b>@</b> 8"	#5@10"	#4@18"
6		6'-0"	10'-0"	#4@18"	#6 <b>@</b> 7"	#5@10"	#4@18"
6		8'-0"	8'-0"	#4@18 <sup>"</sup>	#6@9"	#5@10"	#4@18"
6	"	8'-0"	10'-0"	#4@18"	#7 <b>@</b> 9"	#5 <b>@</b> 6"	#4@18"



DEPARTMENT OF PLANNING & GROWTH MANAGEMENT Raymond N. Shumaker, Jr. Oct 5, 2022

APPROVED:

CHIEF OF CODES, PERMITS, & INSPECTION SERVICES LBIL-

Oct 5, 2022

PROFESSIONAL ENGINEER

DATE

DATE

1"CLR

STANDARD DETAIL

PRECAST CONCRETE **VAULTS FOR METERS & VALVES** 

W

4.03

**REVISIONS:** JUNE 1995 SEPTEMBER 2022