



**NOTES:**

1. BLOWOFF SHALL BE LOCATED IN THE FIELD AS DIRECTED BY THE ENGINEER'S REPRESENTATIVE.
2. THRUST BLOCK TO BE POURED AGAINST UNDISTURBED EARTH.
3. THE PRICE FOR A BLOWOFF ASSEMBLY SHALL INCLUDE 6 FEET OF PIPE.
4. PROVIDE A LAYER OF V-BIO POLYETHYLENE BETWEEN PIPE FITTINGS AND CONCRETE.
5. PROVIDE A 1 INCH CORPORATION TAP WITH A 1 INCH CURB STOP & BOX WITH A 1 INCH DRAIN PIPE INTO GRAVEL UNDER DRAIN. ("K" COPPER ONLY)



**CHARLES COUNTY GOVERNMENT**  
 DEPARTMENT OF PLANNING & GROWTH MANAGEMENT  
 APPROVED: Raymond N. Shumaker, Jr. Oct 5, 2022  
Raymond N. Shumaker, Jr. (Oct 5, 2022 12:20 EDT)  
 CHIEF OF CODES, PERMITS, & INSPECTION SERVICES DATE  
J. B. ... Oct 5, 2022  
 PROFESSIONAL ENGINEER DATE

STANDARD DETAIL  
  
 WATER MAIN BLOWOFF

W
5.01
REVISIONS:
JUNE 1995
SEPTEMBER 2022