



## NOTES:

- PRECAST CONCRETE f'C x 5000 PSI @ 28 DAYS
  REINFORCEMENT SHALL CONFORM TO ASTM C-478
  CAST LIFT LUGS ARE REQUIRED FOR 4" AND 6" RINGS.
- 4. INSTALL MORTAR NOT LESS THAN 1/4 INCH THICK BETWEEN RINGS.RED FOR 4" AND 6" RINGS.

