


D	W
3" & 4"	12"
6"	11"
8"	10"
10"	9"
12"	8"
15"	8"
16" & 18"	8"
20" & 21"	8"
24"	12"



NOTES:

1. SEE DETAIL M/2.04 FOR GRANULAR BEDDING REQUIREMENTS FOR DUCTILE IRON PIPE LARGER THAN 24" DIAMETER.
2. MAXIMUM CLEAR TRENCH WIDTH SHALL BE 2W PLUS THE OUTSIDE DIAMETER OF THE PIPE.
3. IF BEDDING IS REQUIRED, PROVIDE 6 INCHES OF ASTM C33 NO. 67 CRUSHED OR WASHED STONE.
4. IF DUCTILE IRON IS UTILIZED FOR SANITARY SEWER, THEN APPROVED BEDDING IS REQUIRED TO THE TOP OF THE PIPE.

CHARLES COUNTY GOVERNMENT

DEPARTMENT OF PLANNING & GROWTH MANAGEMENT

APPROVED:

[Signature] 6/29/95
DIRECTOR OF DEVELOPMENT SERVICES DATE

[Signature] 6/29/95
WATER / SEWER ENGINEER DATE

STANDARD DETAIL

TRENCH WIDTHS
FOR DUCTILE IRON
WATER MAIN

REVISIONS:

M
2.03

104